

Sr.no	Description	Unit	QTY	Rate to be quoted by the Contractor
1	XLPE INSULATED HT ARMoured CABLES (LOOSE):			
	Supply & laying of Circular Aluminium Conductor screened with extruded semiconducting compound, XLPE insulated, insulation screened with extruded semiconducting combination in combination with copper tape (0.3KA for 1sec.) cores laid up, FR PVC inner sheathed, galvanized steel strip armoured and overall FR PVC sheathed cable confirming to IS:7098 (Part-2), 2011 working voltage 11KV(E) grade to be laid loose in the existing trench or pipe:-			
1.a	HT Cable Overall size 300sq.mm (3Core)	Meter	550	
2	Supply and erection of Double Walled Corrugated (DWC) HDPE pipe to be laid 2mtr. below ground level including excavation placing the pipe in position and back filling with excavated soil etc. of the required size:-			
2.a	Double Walled Corrugated HDPE Pipe 160/ 136mm (Outer/ Inner dia.)	Meter	550	
3	S/E of Heat shrinkable cable end termination/ Straight through joint kit for 11 KVA /6.6 KV (E) XLPE Cables as approved & desired by Engineer in charge:-			
3.a	Heat Shrinkable End Termination for cable size 240-400 sq. mm, 3Core (Outdoor Type)	Each	2	